



Project

Framptons Ltd

Brief

Clean & coat asbestos roof and line gutters

Value

£ 100,000+

Solution

Framptons Limited had been struggling with 3 leaking asbestos cement roofs for a number of years, with reactive maintenance being carried out when necessary. A long term solution was required. Total roof area 3000m²

Overclad was not an option as the landlord did not like the idea of putting a roof on top of another (rightly so). We opted for a simple, pressure clean, water filtering of waste water to 5 microns, prep & coating

The major area of water ingress was the because of extreme weather causing the Asbestos to degrade. This is the main problem we see with roofs.

The project was completed behind schedule due to the great British weather but was on budget. The roof is now guaranteed for 10 years.